

ADDENDUM # 1

To RFP # 2016-102

CABLING PROJECT

February 10, 2016

Changes or Clarifications-

- Computer Lab
 - (45) Cables total, (43) Cat 6 and (2) Cat 6A. 38 work stations, 4 center room in-ground, 1 teacher station, 1 WAP
- Gym
 - (4) Cat 6A cables total, (2) cable per each of the (2) WAP locations.
 - (3) Cat 6 cables total in music room.
 - (2) Cat 6 cables total in back of kitchen at workstation.
 - (2) Cat 6 cables for camera to be mounted. (1) in back of building behind kitchen and (1) front of building on the great wall.
- Library
 - (12) Cables total, (10) Cat 6, (2) Cat 6A
- South/West Portables (E, F, G, H)
 - (18) Cables total, (2) Cat 6 and (2) Cat 6A to each classroom, and (2) additional Cat 6 cables to building E for video camera that will be mounted on the outside roof of building.
- South/East (P1-P4)
 - (16) Cables total, (2) Cat 6 and (2) Cat 6A to each classroom

- South/East Portables Special Needs
 - (7) Cables total, (5) Cat 6 and (2) Cat 6A.
 - Has existing pathways between buildings.
 - Add raceway as needed for teacher location.
 - Re-terminate existing data station cabling in new cabinet on new patch panel.

Vendor to sign as acknowledgment of receipt and return with bid/RFP.

Signature : _____

Date: _____

Company Name (please print) _____